

AA Fencing Co.

4168 FM 85
Ennis, Texas 75119
214-934-4525
aafencing@att.net

ESTIMATE

INVOICE TO
Peach Tree Apts
1402 S Peach Tree
Mesquite, Tx

SHIP TO

ESTIMATE NO. 1407
DATE 07/16/2019
EXPIRATION DATE 08/15/2019

NO.	DATE	ACTIVITY	QTY	AMOUNT
1		Installation Remove approximately 980 Lft of 6' perimeter R-Panel fence. Install approximately 980 Lft of 8' perimeter board on board wood fence. (1×6×8) Install approximately 980 Lft of kicker board on botton of fence. (2×6 pressure treaded) Wood fence will consist of : 2x8 top cap 2 layers of trim Star decor Metal post in concrete 2x4 rails (4) Metal brackets Lag screws and caps All wood will be stained (med brown) NOTE: the city permit and drawings is included in the above cost. 50% Deposit before project begins, balance due at the completion of job. Job is warranty for one year.	1	66,500.00

SUBTOTAL

TOTAL

\$66,500.00

Accepted By

Accepted Date