



City of Mesquite, Texas

Legislation Details (With Text)

File #: 20-4992 **Version:** 1 **Name:** Bid 2020-075 - S.Mesquite Creek Gabion Repair
Type: Agenda Item **Status:** Passed
File created: 8/27/2020 **In control:** City Council
On agenda: 9/21/2020 **Final action:** 9/21/2020
Title: Bid No. 2020-075 - South Mesquite Creek Gabion Stabilization by Sheet Piling.
(Authorize the City Manager to finalize and execute a contract with low bidder JB & Co., LLC, in the amount of \$573,700.00)

Sponsors:

Indexes:

Code sections:

Attachments: 1. Recommendation Letter, 2. Bid Tabulation - 2020-075, 3. Location Map, 4. Photo - Gabion wall at time of construction, 5. Photo - Aug 28, 2020, indicating settlement of Gabion Wall.pdf

Date	Ver.	Action By	Action	Result
9/21/2020	1	City Council	Approved	Pass

Bid No. 2020-075 - South Mesquite Creek Gabion Stabilization by Sheet Piling.
(Authorize the City Manager to finalize and execute a contract with low bidder JB & Co., LLC, in the amount of \$573,700.00)

Name of Department

Public Works

Project/Budgeted Amount

\$590,911.00

Sum of Bid/Bid Amount

\$573,700.00

Background:

Valley Creek Estates Addition is located on Pioneer Road on the south side of South Mesquite Creek, south and across Pioneer Road from Valley Creek Park. Valley Creek Estates Addition's infrastructure was constructed in 1986. In March of 2001, erosion in South Mesquite Creek had impacted the franchised utilities and backyards of homes in Valley Creek Estates that are adjacent to the creek. In response, plans were developed to stabilize the south bank behind the affected homes and a gabion wall stream bank stabilization project was constructed in the summer of 2003. The gabion wall has stabilized the creek bank and protected the private properties and endangered utilities for approximately 15 years. However, in November of 2018, homeowners alerted City staff that the floor of the creek had eroded downward four to five feet undermining the support of the gabion wall and a slope failure had started. Staff began evaluating repair options, consulted with engineers and contractors and in August of 2019, City Council approved a design contract for the repair of the failing gabion wall with Halff Associates. The project was designed and bid in July 2020. Bid notices were broadcast through the BidSync electronic bidding system, posted on the City's website and an Advertisement for Bid was published in the *Daily Commercial Record* newspaper. A total of three responsive bids were received.

This contract will repair and stabilize the gabion wall by installing sheet piling at the base of the gabion wall and pouring concrete between the piling and the wall. Due to the close proximity of the homes, the sheet piling will be installed using the “push” method to minimize vibration and impact during the construction. After repairs are made, the grassed area at the top of the gabion wall will be regraded and the storm sewer will be repaired by City forces.

Financial Implications

This project is funded through the Drainage Utility District.

Recommended/Desired Action

Staff recommends award to low bidder JB & Co., LLC.

Attachment(s)

Recommendation Letter

Bid Tabulation

Location Map

Photo - Gabion wall at time of construction

Photo - August 28, 2020, indicating settlement of Gabion Wall

Drafter

Steve Glass, P.E.

Head of Department

Matthew Holzapfel, P.E.